

Anker Valley

Tamworth

Three years of planning resulted in the construction of retaining walls to complement the layout of a large housing development



The project

Bellway Homes undertook the development of a large housing development in Tamworth, close to their offices. Even though the actual construction of the Permacrib walls took place in 2018, Phi Group started the design process and discussions with Bellway Homes and their engineers Travis Baker, in late 2015.

The challenge

The main challenge was identifying during the design stage how the two Permacrib retaining walls interacted with other structures on site, such as garages and housing plots. Through continued co-ordination, a suitable retaining wall layout was arrived at. The construction was more straightforward, with long runs of Permacrib retaining walls to build.

The solution

Two Permacrib timber crib retaining walls were constructed on site, with a total length of 270m, an average retained height of 4.0m, and a face area of nearly 1,000m². A perfect project to highlight the economic benefit Permacrib has over traditional methods of retaining. Speed of construction is a key benefit, with 25m² a day face area constructed with ease.

Project facts

Owner(s)

Bellway Homes

Keller business unit(s)

Phi Group

Main contractor(s)

Bellway Homes

Engineer(s)

Travis Baker

Solutions

Slope stabilisation

Markets

Residential

Techniques

Retaining structures

Email address

foundations.uk@keller.com

Phone number

02476 511266