

Horfield Cutting

Bristol

The Great Western Route is undergoing a period of modernisation with the upgrading of infrastructure to make journeys faster and services more reliable. Part of this scheme is the Horfield Cutting where an extra lane is being added to ease a bottleneck in the rail system.



The project

MJ Church, the civils contractor for Vinci Construction, contracted Phi Group to install a gabion retaining wall nearly 1,000m long and up to 5.0m high in places alongside the extra lane.

The challenge

As with all rail projects undertaken next to a live railway track, health and safety and method of working is of utmost importance. The delivery and storage of materials is a consideration to, with double handling of materials often required. A tight build programme also added to the complications.

The solution

Woven mesh gabion baskets were specified by the client, but Phi Group proposed they be changed to the welded mesh gabion baskets that are quicker to install. The baskets are then filled with 6G gabion stone to give them the required mass. Upvc sleeves were installed within the baskets as they were being installed, so soil nails could be installed through the baskets to further stabilise the slope once the gabions were finished. Hand placing of the gabion stone to the front face ensures a great looking finish to the wall.

Project facts

Owner(s)

Network Rail

Keller business unit(s)

Phi Group

Main contractor(s)

Vinci Construction

Solutions

Containment

Markets

Infrastructure

Techniques

Retaining structures

Email address

foundations.uk@keller.com

Phone number

02476 511266